


## **GENERAL NOTES:**

- A. REFER TO PROJECT MANUAL FOR ADDITIONAL REQUIREMENTS.
- B. COORDINATE WORK WITH OTHER SITE RELATED DEVELOPMENT DRAWINGS.
- C. PRIOR TO INSTALLATION, GENERAL CONTRACTOR TO CONFIRM THAT LIGHT POLES, LANDSCAPING AND UTILITIES DO NOT CONFLICT WITH SIGN LOCATION SHOWN. IF ANY POTENTIAL CONFLICT IS DISCOVERED, GENERAL CONTRACTOR TO CONTACT THE O'REILLY PROJECT ADMINISTRATOR BEFORE PROCEEDING.

## COVERAGE DETAIL:

1. IRRIGATION HEAD SHALL BE PLACED TO PROVIDE 100 % OVERLAP HEAD-TO-HEAD COVERAGE.



INSTALLED ON IRRIGATION SYSTEM.


2. A RAIN SENSOR AND ANTI-FREEZE ASSEMBLY SHALL BE

- 3. THE IRRIGATION CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A COMPLETE AND OPERABLE SYSTEM FOR THE IRRIGATION OF ALL LANDSCAPE PLANTING(S) AND DESIRED COVERAGE AREAS ON SITE.
- 4. THE IRRIGATION CONTRACTOR IS FULLY RESPONSIBLE FOR THE WORK UNTIL OWNER GIVES FINAL ACCEPTANCE.
- 5. NO WATER TO BE SPRAYED ON SIDEWALK, PARKING LOT, ROAD OR ADJACENT PROPERTY. ADJUST ARC AND RADIUS OF REQUIRED SPRINKLERS AS NEEDED.
- 6. ALL CIRCUIT PIPE IS TO BE CLASS 160 PVC OR HIGHER
- 7. ALL MAIN FITTINGS SHALL BE REINFORCED WITH 2000PSI POURED CONCRETE THRUST BLOCKS.
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTING THE REQUIRED SYSTEM IN COMPLETE ACCORDANCE WITH ALL APPLICABLE CODES, ORDINANCES, AND LAWS. ANY MODIFICATION MADE AFTER INSTALLATION TO CONFORM WITH SAID CODES, LAWS AND ORDINANCES SHALL BE PERFORMED AT CONTRACTORS EXPENSE AT NO ADDITIONAL COST TO
- 9. DRIP IRRIGATION TO BE PROVIDED IN VINE POCKET FOR TRELLIS ON THE FRONT OF THE BUILDING.

## LANDSCAPE SYMBOLS LEGEND

REFER TO SURVEY FOR EXISTING CONDITION SYMBOLS LEGEND **NEW BUILDING CONSTRUCTION** AREA OF CONCRETE AREA OF PAVING AREA OF DESIRED IRRIGATION COVERAGE NEW POLE SIGN LOCATION NEW CONCRETE PAVING BLOCK NEW LIGHT POLE LOCATION  $\rightarrow \times \times$ NEW FENCE CONSTRUCTION

**NEW MASONRY FENCE CONSTRUCTION** 



LUNDBI

MAS

AUTO

COMM # 3484

DATE: 9-27-13 DATE: